

ASPIRE STONE FABRICATIONS

Pre-template checklist

We take pride in customer satisfaction and quality craftsmanship. Our goal is to make your project a success. To ensure we obtain an accurate field measure / template, the following conditions and specifications need to be complete before the template appointment. Please take a moment to review and check off each paragraph. Please feel free to call us with any questions on 01934 257217 as you go through the checklist.

All material, edge detail and overhang dimensions have been selected by customer. Excessive overhands (greater than 300 mm) may need supports (not supplied by Aspire Stone Fabrications Ltd).

All base cabinets and end panels are fixed in place and have been set level and straight in their permanent locations. It is understood that the base units out of level or out of straightness (including existing base units in remodels) will need to be properly adjusted prior to templating of worktops. Levelling and adjustments of units are NOT included in the worktops price (call for details). Please do not move any units once template is completed.

All existing worktops or temporary worktops must be removed.

All fixtures (i.e. Ranges, Hobs, Taps, pop up sockets etc.) are on site prior to template appointment for measurement purposes.

Sinks MUST BE installed inside the units 1 mm lower than the top of the carcass with 2-3 mm of movement and supported by brackets, frame work or a shelf. Please bear in mind the tap position when building the framework.

If receiving a splash back, all extractor hoods and ranges must be set in their permanent location prior to template appointment.

All plastering/finishing of walls effecting sizes of worktops must be completed.

Boxing in of pipework must be completed prior to template.

Any dresser units that sit on the work surface need to be present at template & the walls need to be clearly marked where upstands should stop and start.

Dresser units should be fitted with adjustable wall brackets and including enough clearance for work surfaces to be slid in place 3 mm higher than worktops.

All shelves will be 'Supply Only' and it will be the responsibility of the customer to install at their own risk.

Window Sills If you are having a window sill installed, your old window sill must be removed prior to templating. The window sill area must be a sound level surface to enable us to install/level and glue your new window sill in place.

Breakfast bars/Seating Areas Please ensure adequate support is available for work-surfaces. Overhanging greater than 300 mm will require additional support. It is normal to cut your island work surface square, please ensure your units are installed square prior to our arrival. If they are not then your overhands will vary.

Plumbing/Electrical work Aspire Stone are not qualified or insured for any plumbing or electrical work. Once your worktop installation is complete your plumber/electrician will need to connect your sink, taps, cookers, hobs, etc. Any works should be delayed 24 hours after installation to allow time for adhesives to go off.

General Water, Electricity and adequate lighting must be available on site.

Customer or Sales Associate MUST BE present at template and install to verify and approve details. If no representative is on site, 30 minutes will be allowed for their arrival otherwise the template will be aborted.

All fall-off material (i.e. sink cut outs, hob cut outs, etc.) is the property of Aspire Stone Fabrications Ltd.

Customer is responsible for removing all items from base units prior to template appointment.

If receiving full wall cladding all socket faces must be removed and the electric supply must be isolated.

It is the responsibility of the customer to ensure that the hob fits with the selected thickness of stone and any additional cutting of the furniture will be down to the client.

Extras – If any extra are added to the template, this may result in a delay to the scheduled installation date.

It is understood that cancelled appointments due to failure to prepare any of the above Checklist items may result in an abort charge of £150 + VAT for template and £250 + VAT for installation.

A tolerance of 30 minutes will be allowed to solve any issues on site before the template will be aborted.

Cancellation of appointments must be advised within 24 hours of the scheduled appointment.

Photos will be taken for Aspire Fabrications records.