

ASPIRE STONE FABRICATIONS

Installation Conditions

FAQ: Your Fitters or to be passed to your customer if supply only

Please ensure you have a company representative or the customer on site on the day of installation to check and sign off the worksurfaces and the completed installation.

If any sink, tap or hob has been re-connected following template they MUST be disconnected prior to intended installation date.

All electrical, gas and sink fittings to be removed prior to installation if they interfere in any way with the installation of stone tops.

Tiling in areas around the worktops MUST take place after the worktop installation.

In the event of plasterwork/paintwork etc. being disturbed during fixing, all subsequent making good costs to be the clients responsibility.

Aspire Stone fitters are not qualified or insured for any plumbing, gas or electrical works.

DO NOT stand on installed worksurfaces. Any damages incurred by this will be chargeable to repair/replace.

To allow joints, sealants to correctly harden/go off we advise leaving the tops for a minimum of 24 hours after our fitting date before other works are carried out including the plumbing of sins, taps and hobs.

The unit carcasses must be level, flat, have sufficient strength and suitability to accept the weight of the stone work surfaces.

Please make sure all routes to the kitchen are clear and safe for delivery. Also that the room is clear of all unessential items and trade.

TOLERANCES

Overhangs

Kitchen door with handle	40 mm	from the carcase
Kitchen door without handle	5 mm	from the door
End/decorative panel (kitchen with handles)	20 mm	from the panel
End/decorative panel (kitchen without handles)	10 mm	from the panel
Undermounted sink	5 – 10 mm overhang	around the sink
Belfast sink	10 - 20 mm	overhang around the sink
Window sill	10 – 20 mm	overhang from the upstand/riser

Aspire Stone allows for a +/- 3 mm tolerance on all overhangs, these tolerances are dependant on cabinetry being fitted with a straight front edge and level.

Cut out positioning

Undermounted sink	As per sink mounted in base unit by kitchen installer
Inset sink	As per kitchen installer markings for location
Tap hole	as per manufacturers guidelines to suit the base unit
Hob cut out	centra to relevant base unit

Upstands

Standard upstands will be 20 mm thick x 100 mm , standard height can be changed but minimum of 50 mm height. Material thickness can be reduced at a cost.

Finishing

We will silicone to the base of the upstand using a coloured silicone, if you have any preference discuss with fitter on arrival.

Upstands/splashback edges that meet the wall could have a gap, your decorator will need to caulk this and decorate to it, this is NNOT something we do.

Jointing

3 mm or less in width
Coloured adhesive
Material thickness has a +/- 2 mm tolerance so may require levelling when jointing and also blending in

Splash backs

3 mm tolerance gap required under / against cabinets

Overall cut tolerance

Our machinery works to industry standard +/- 3 mm on cuts on all pieces and apertures.

Photos will be taken for Aspire Fabrications records.